



- Accessory for Loadstar Distribution Boards. Suitable for use with 2 x 125A type B Meter Ready (MR) Distribution Boards. (Vertically mounted)
- Kit consists of 3 phase and neutral connection cables, cable clamps and shrouding.
- 125A integral meter kits to be ordered separately
- Maximum 3 phase load on upper board should not exceed 100A.
- Provides separate lighting and combined load readings. Power load calculated by subtracting top section load, from total load measurement.

**Product Specification Data**

Revision Date: 15/10/2021

Nominal current (In)	125 A
CE Conformity	Yes
WEEE Symbol	No
UKCA Conformity	Yes

Although every effort has been made to ensure accuracy in the compilation of the technical detail within this datasheet, specifications and performance data are constantly changing. Latest details can be obtained from the Electrium website.